

(FILE NO.CWK/1/2021)

**ESTIMATE****SUBRAMONIYAM HALL ROOF WORK**

SI.NO	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	Dismantling cement asbestos or other hard board ceiling or partition walls including stacking of serviceable materials and disposal of unserviceable materials elsewhere	Sqm	1110	60	66600
2	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required 0.63 mm thick with zinc coating not less than 275 gm/ m <sup>2</sup>	Sqm	630	1280	806400
3	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete 0.63 mm thick with zinc coating not less than 275 gm/m <sup>2</sup>	Mtr	35	994	34790
4	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. Purlins 2" x2"	Kg	2430	143	347490
5	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead	Sqm	135	77	10395

6	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer ) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joints with white cement and matching pigments etc., complete. size of tile 500 x 500mm	Sqm	135	1180	159300
7	Providing and fixing false ceiling with 9 mm thick TKT panel board ceiling of approved quality in aluminium frame work with necessary screws etc complete ( inclusive of aluminium frame work)	Sqm	480	1250	600000
<b>Total Estimated Cost</b>					<b>2024975</b>

(Exclusive of GST)

**Quoted Amount: I agree to carry out the work at Estimate Cost.....% (in words)..... above/below estimate cost.**

\* score words not applicable

**CONTRACTOR**

(To be signed)