

TENDER FORM

From

To

The Hon.Secretary & Educational Advisor,
Bharatiya Vidya Bhavan,
Bhavan's Towers, Kattu Road,
Poojappura P.O. Thiruvananthapuram -12

Sir,

I/We hereby tender to carry out the works, under the annexed general conditions of contract; the whole of the work referred to and described in the attached specification and schedule, or any portion thereof, as may be decided by Bharatiya Vidya Bhavan, at the **percentage rates** quoted. The work will be completed within the time and at the places specified in the schedule.

*I/We am/are remitting/have separately remitted the required amount of Rs./- (Rupees only) as Earnest Money.

Yours faithfully

Signature
Name of Tenderer

Address for communication with Mobile Phone No.

.....
.....
.....
.....

Date:

*(To be scored in cases where no Earnest Money Deposit is furnished)

(General Conditions on the reverse)

ANNEXURE -I

GENERAL CONDITIONS

Sealed Tenders are invited from registered Contractors for the following works of Bharatiya Vidya Bhavan.

Sl. No	Name of work	Estimate/PAC	Earnest Money Deposit
1	Replacement of Roof of Subramaniam Hall of BVB Sr.Sec.School Vattiyorkavu (Kodunganoor) (File No. CWK/1/2021)	Rs. 20,24,975/-	Rs.20,250/-
2	Providing Roof Truss above Munshi Block in BVB Sr.Sec.School, Kodunganoor (File No.CWK/2/2021)	Rs.5,69,400/-	Rs.5,700/-

Tender Forms can be downloaded freely from the website from 01.12.2021: <www.bhavanstrivandrum.com>. EMD is accepted in the form of DD drawn in favour of Hon. Secretary & Educational Advisor, Bharatiya Vidya Bhavan, payable at SBI Poojappura, Thiruvananthapuram.

The last date of receipt of filled up Tender form is fixed as **15.12.2021, 3.00pm**

Payment will be made on completion of the work in all respects on submission of the bill as certified by the Engineering Consultant. 10% of the Bill amount will be retained from the bill amount which will be released only after the defects liability period of 6 months.

The Tender should be submitted on the mode of **Percentage Quoting**.

The Tender **Opening date** is fixed as **4.pm on 16th December 2021**.

The successful bidder of each work will have to execute an Agreement in Stamp paper worth Rs.500/-. Security Deposit @5% of PAC, is to be made by the successful bidder in the form of DD, FD of scheduled bank/KSFE duly pledged in favour of Hon. Secretary, Bharatiya Vidya Bhavan and will be released on expiry of contract.

The last date of completion of work is fixed as **31st of Jan. 2021**.

Sd/-

**Hon. Secretary & Educational Advisor
(Tender Inviting Authority)**

**Providing Roof Truss above Munshi Block in BVB
Sr.Sec.School, Kodunganoor**

1. Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with a special shaped washers etc. complete. Hot finished welded type tubes kg.

a) Rafter (80 x 40 x 2 mm) @ 3 mc/c

b) Hip Rafter (80 x 40 x 2 mm)

c) Purlin (40 x 25 x 2mm) @ 1.5 mc/c

d) Truss supporters (80 x 40 x 2 mm)

e) Principal Rafter (80 x40 x 2 mm)

f) Post (100mm dia tube) @ 3m c/c of height 1.5m to 1.8m

g) Base plate (150 x150 x6mm) including nuts and bolts.

2. Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.5mm (+0.05%) total coated thickness with Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metres or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5 x 55mm) with EPDM seal, complete upto any pitch in horizontal/vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.

3. Providing ridges or hips of width 60cm overall width plain G.S sheet fixed with polymer J or L Hooks, bolts and nuts 8mm dia G I limpet and bitumen washers complete. 0.63mm thick with Zinc coating not less than 275 gm/m².

4. Providing and fixing 15cm wide, 45 cm overall semi-circular plain GS sheet gutter with iron brackets 40x3mm size, bolts nuts and washers etc

including marking necessary connections with rain water pipes complete.
0.63 mm thick with Zinc coating, not less than 275gm/m².

5. Providing and fixing 100 mm dia down water pipes all around.

6. Providing and fixing poly carbon sheet roof 1.5m wide starting from the end of the centre RCC slab edge.

Total area of roof = 520 Sq.m (Area will be measured horizontally)

Rate per Sq.m = Rs.1095/-

Total estimated cost = 520x1095 = 5,69,400/=

Quoted amount: I agree to carry out the work at *Estimate cost/_____% (in words)_____/above/below estimate cost.

Contractor

(To be signed)

*score the words not applicable